
# GENESEE 6 SOLAR ARRAY

# 8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

<u>F</u>	PROJECT DATA	
PARCEL INFORMATION		
APPLICANT	NY CDG GENESEE 6, LLC	
PARCEL ADDRESS	8244 BAT- STAF TWLN RD BATAVIA, NY 14020	
POI LONGITUDE AND LATITUDE	N 43° 00' 53.32" W 78° 07' 59.73"	
TAX NUMBER	01-02-115	
NUMBER OF TABLES	234	
NUMBER OF PANELS	11,154	
NUMBER OF INVERTERS	20	
SYSTEM SIZE (DC)	6.07 MW (DC)	
SYSTEM SIZE (AC)	5 MW (AC)	
GPS COORDINATES	N: 43.015029 W: -78.127823	
AVERAGE SITE ELEVATION	±799'	
PARCEL AREA	±128 ACRES	
EQUIPMENT PAD AREA	±600 SF	
FENCED AREA	±26.70 ACRES	
DISTURBED AREA	±31.55 ACRES	
LEASE AREA	±32.74 ACRES	
ROAD LENGTH	±1,058 FT	
CHAIN LINK FENCE	±6,579 FT	
LEVEL SPREADER (LF)	±3,540 FT	
DOUBLE SWING GATE COUNT	3	
MAN GATE COUNT	3	
MODULE TYPE	JAM72D30-545/MB	
INVERTER TYPE	SOLECTRIA XGI 1500 250/250-600	

IING INFORMAT	<u> TION</u>
<u>REQUIRED</u>	PROPOSED
TOWN OF	STAFFORD
HTTPS://TOWNOFSTAFFO	RD.ORG/DEPARTMENTS/ZONING-CO
(IP) INDUST	TRIAL PARK
200 FT	200 FT
200 FT	200 FT, 100 FT*
200 FT	200 FT, 50 FT*
<u>-</u>	40 FT
-	7 FT
	REQUIRED TOWN OF HTTPS://TOWNOFSTAFFO (IP) INDUST 200 FT 200 FT

\*AREA VARIANCE APPROVED VIA CH. 182, ART VII, §182-49.K.(3)



#### **DRAWING INDEX**

C001 GENERAL NOTES AND LEGEND

C101 EXISTING CONDITIONS PLA

C201 OVERALL SITE AND UTILITY PLAN

C202 SITE AND UTILITY PLAN

C203 LANDSCAPE PLAN

C301 EROSION AND SEDIMENT CONTROL PLAN

C401 OVERALL GRADING PLAN

C402 GRADING PLAN

C501 CONSTRUCTION DETAILS

C502 CONSTRUCTION DETAILS

C503 CONSTRUCTION DETAILS

C504 CONSTRUCTION DETAILS

C601 DECOMMISSIONING PLAN (PHASE 1)

C602 DECOMMISSIONING PLAN (PHASE 2)

# NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024 NOVEMBER, 2023 REVISED: JULY 14, 2025





#### GENERAL NOTES

- 1. THE CONTRACTOR ALONE SHALL BE RESPONSIBLE TO LOCATE UTILITIES OUTSIDE THE RIGHT-OF-WAY INCLUDING PRIVATE ROADS.
- 2. SITE DRAINAGE, INCLUDING THE PROJECT SITE AND ADJACENT PRIVATE AND PUBLIC ROADWAYS, DRIVES, PARKING AREAS OR PROPERTIES SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
- 3. THE CONTRACTOR SHALL BE RESPONSIBLE FOR SUPPLYING ALL MATERIALS, TOOLS AND EQUIPMENT, INCLUDING SPECIAL CUTTING DEVICES, NECESSARY TO PERFORM THE WORK CONTAINED IN THIS CONTRACT.
- 4. THE SIZES AND MATERIAL OF CONSTRUCTION OF STORM SEWERS ARE REPUTED. THE CONTRACTOR SHALL VERIFY SIZES OF ALL UTILITIES WHERE CONNECTIONS TO SAID EXISTING UTILITIES ARE REQUIRED. EXCAVATION TO VERIFY THESE UTILITIES SHALL BE MADE AT NO ADDITIONAL COST TO THE OWNER.
- 5. THE CONTRACTOR SHALL PROTECT ALL EXISTING SITE AMENITIES NOT DESIGNATED FOR REMOVAL.
- 6. UNLESS OTHERWISE INDICATED ON THE PLANS OR DIRECTED BY THE ARCHITECT/ENGINEER, THE CONTRACTOR IS RESPONSIBLE FOR PRESERVING AND PROTECTING FROM DAMAGE ALL TREES, SHRUBS AND PLANTS IN THE VICINITY OF THE PROPOSED WORK.
- 7. THE CONTRACTOR SHALL PROTECT AND SUPPORT ALL EXISTING UTILITIES DESIGNATED TO REMAIN FOR THE DURATION OF THE CONTRACT.
- 8. ANY SITE AMENITY, UTILITY, STREET APPURTENANCE, OR OTHER ITEM WHICH BECOMES DAMAGED AS A RESULT OF THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED OR REPLACED IN-KIND BY THE CONTRACTOR AS DETERMINED BY THE PROJECT MANAGER OR ARCHITECT/ENGINEER AND AT NO ADDITIONAL COST TO THE OWNER.
- 9. PERMANENT WARNING LABELS TO BE PROVIDED BY THE INSTALLER AT ALL PV SYSTEM DISCONNECTING MEANS IN COMPLIANCE WITH ANSI ZZ535.4, UL 969, NFPA 70 (2017) SECTIONS: 110.20, 690.13(B), 690.53 AND 690.54.

#### SURVEY NOTES

- 1. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO BID. NO ALLOWANCE WILL BE MADE FOR ADDITIONAL COSTS DUE TO CONTRACTOR'S FAILURE TO VERIFY EXISTING CONDITIONS,
- 2. THE CONTRACTOR SHALL LOCATE, MARK, SAFEGUARD AND PRESERVE ALL SURVEY MARKERS AND RIGHT-OF-WAY MARKERS IN THE AREA OF CONSTRUCTION.
- 3. ANY IRON PINS, MONUMENTS OR OTHER ITEMS DEFINING PROPERTY LINES WHICH ARE DISTURBED BY CONSTRUCTION OPERATIONS SHALL BE PROPERLY TIED AND ACCURATELY RESET BY A NYS LICENSED SURVEYOR UPON COMPLETION OF THE WORK.
- 4. HORIZONTAL DATUM BASED OFF NAD83-W.
- 5. ELEVATIONS BASED ON NGVD'88 DATUM US FT.

#### **DEMOLITION NOTES**

- 1. CONTRACTOR SHALL FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO BID. NO ALLOWANCE WILL BE MADE FOR ADDITIONAL COSTS DUE TO CONTRACTOR'S FAILURE TO VERIFY EXISTING CONDITIONS AND DIMENSIONS.
- 2. PRIOR TO THE START OF CONSTRUCTION, THE CONTRACTOR SHALL NOTIFY DIG SAFELY NEW YORK AT 811 TO REQUEST UTILITY STAKEOUT OF ALL PUBLIC UTILITIES.
- 3. THE HORIZONTAL AND VERTICAL LOCATION OF ALL EXISTING ABOVE GROUND AND BELOW GROUND UTILITIES, STRUCTURES, AND APPURTENANCES SHOWN ON THE PLANS ARE APPROXIMATE AND ARE NOT GUARANTEED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR DETERMINING THE EXACT HORIZONTAL AND VERTICAL LOCATION OF ALL UTILITIES, STRUCTURES, AND APPURTENANCES IN THE PATH OF AND ADJACENT TO THE PROPOSED WORK
- 4. SITE DRAINAGE, INCLUDING THE PROJECT SITE AND ADJACENT PRIVATE AND PUBLIC ROADWAYS, DRIVES, PARKING AREAS OR PROPERTIES SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PERIOD.
- 5. CONTRACTOR SHALL PROTECT AND SUPPORT ALL EXISTING UTILITIES DESIGNATED TO REMAIN FOR THE DURATION OF THE CONTRACT.
- 6. THE CONTRACTOR SHALL NOTIFY THE LOCAL GOVERNMENT, LOCAL FIRE DEPARTMENT AND THE NEW YORK STATE DEPARTMENT OF ENVIRONMENTAL CONSERVATION (NYSDEC) AS NECESSARY AND SHALL OBTAIN ANY REQUIRED PERMITS PRIOR TO BEGINNING WORK. COPIES OF ANY REQUIRED PERMITS SHALL BE PROVIDED TO THE OWNER PRIOR TO BEGINNING THE WORK.
- 7. CONTRACTOR SHALL REMOVE FROM SITE, MATERIALS NOT INDICATED TO BE SALVAGED INCLUDING ALL DEBRIS. ALL REMOVED MATERIALS SHALL BECOME THE PROPERTY OF CONTRACTOR WHO SHALL LEGALLY DISPOSE OF SAME.
- 8. ALL TREES, SHRUBS AND PLANTS DESIGNATED TO REMAIN AND DISTURBED BY CONSTRUCTION OPERATIONS, SHALL BE REPLACED IN-KIND AS DIRECTED BY THE ARCHITECT/ENGINEER AND/OR OWNER'S DESIGNATED REPRESENTATIVE AT NO ADDITIONAL COST TO THE OWNER.
- 9. THE CONTRACTOR SHALL MAINTAIN SAFE VEHICULAR AND PEDESTRIAN ACCESS TO THE EXISTING BUILDINGS FOR THE DURATION OF THE CONTRACT.
- 10. WHEN EXISTING CONSTRUCTION WHICH IS TO REMAIN IS DAMAGED DURING THE COURSE OF CONSTRUCTION AS A RESULT OF CONTRACTORS WORK, IT SHALL BE REPAIRED AND/OR REPLACED WITH SIMILAR OR LIKE MATERIALS AS MUCH AS POSSIBLE, AT NO COST TO THE OWNER. ALL REPAIRS AND/OR REPLACEMENTS WILL BE SUBJECT TO OWNERS APPROVAL.
- 11. COORDINATE LOCATION OF TEMPORARY CONSTRUCTION FENCE AND TEMPORARY STONE STAGING AREA WITH OWNER

#### SITE NOTES

MANAGER IN WRITING.

- 1. WELL COMPACTED SUBGRADE SHALL BE UTILIZED UNDERNEATH CONSTRUCTION OF PAVEMENT AND CONCRETE BASES.
- 2. ALL STAKEOUT FOR THE PROPOSED SITE IMPROVEMENTS SHALL BE COMPLETED BY A
- NEW YORK STATE LICENSED LAND SURVEYOR.

  3. IF ANY DISCREPANCIES ARE NOTED BETWEEN THESE CONSTRUCTION DOCUMENTS AND INFORMATION PROVIDED OR AN ERROR IS SUSPECT, IT SHALL BE IMMEDIATELY

REPORTED TO THE CONSTRUCTION MANAGER AND LABELLA ASSOCIATES PROJECT

4. ANY PROOF-ROLLING OF EXPOSED SUBBASE BY A MINIMUM 10 TON SMOOTH DRUM ROLLER SHALL BE DONE UNDER THE GUIDANCE OF, AND OBSERVED BY, QUALIFIED ENGINEERING PERSONNEL PRIOR TO PLACEMENT OF SUBBASE MATERIAL. THE ROLLER SHOULD BE OPERATED IN THE STATIC MODE AND COMPLETE AT LEAST TWO (2) PASSES OVER THE EXPOSED SUBGRADES.

#### GRADING NOTES

- 1. THE CONTRACTOR SHALL CONFORM TO THE REQUIREMENTS OF OSHA, AND ANY OTHER AGENCY HAVING JURISDICTION WITH REGARD TO SAFETY PRECAUTIONS WITH TRENCHING OPERATIONS. THE REQUIREMENTS SET FORTH HEREIN ARE INTENDED TO SUPPLEMENT REQUIREMENTS ESTABLISHED BY THESE AGENCIES. IN THE CASE OF A CONFLICT BETWEEN REQUIREMENTS OF OTHER JURISDICTIONAL AGENCIES AND THESE DOCUMENTS, THE MORE STRINGENT REQUIREMENT ON THE CONTRACTOR SHALL APPLY.
- CONTRACT AND SHALL BE PROVIDED AT NO ADDITIONAL COST TO THE OWNER.

  3. ALL TRENCHES THROUGH PAVEMENT SHALL BE SAW CUT PRIOR TO EXCAVATION. PRIOR

2. SHEETING, IF REQUIRED DURING CONSTRUCTION, IS CONSIDERED TO BE PART OF THIS

- ALL TRENCHES THROUGH PAVEMENT SHALL BE SAW CUT PRIOR TO EXCAVATION. PR
  TO RESTORATION ROUGH/JAGGED EDGES SHALL BE SAW CUT TO PROVIDE A
  CONSISTENT EDGE.
- 4. VOIDS LEFT BY UTILITY OR STRUCTURE REMOVAL OR GRUBBING OPERATIONS SHALL BE BACKFILLED AND PROPERLY COMPACTED WITH STRUCTURAL FILL (NYSDOT ITEM 304.12) IN AREAS UNDER AND WITHIN 5 FEET HORIZONTALLY OF ALL STRUCTURES, BUILDINGS AND PAVEMENTS. IN GRASSED AREAS, VOIDS LEFT SHALL BE FILLED AND PROPERLY COMPACTED WITH SUITABLE ON-SITE OR IMPORTED EARTHEN BACKFILL. ALL DISTURBED AREAS SHALL BE RESTORED.
- 5. THE CONTRACTOR SHALL DEWATER ALL EXCAVATIONS TO PREVENT THE INTRODUCTION OF GROUNDWATER INTO THE TRENCHES/EXCAVATIONS. PROVIDE ALL EQUIPMENT NECESSARY TO MAINTAIN THE GROUNDWATER LEVEL AS NECESSARY.
- 6. THE CONTRACTOR SHALL PLACE AT MINIMUM 6 INCHES OF CLEANED SCREENED TOPSOIL IN ALL DISTURBED AREAS PRIOR TO SEEDING

#### **EROSION AND SEDIMENT CONTROL NOTES**

- 1. ALL EROSION CONTROL MEASURES SHALL BE IN ACCORDANCE WITH NEW YORK STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, AND LOCAL GOVERNING SOIL AND WATER CONSERVATION AGENCY RECOMMENDATIONS AND STANDARDS. CONTRACTOR SHALL SUBMIT PROPOSED EROSION CONTROL PLAN INCLUDING SEQUENCING OF WORK TO THE ENGINEER FOR REVIEW PRIOR TO START OF
- 2. UTILIZE CONSTRUCTION METHODS/TECHNIQUES, WHICH WILL LIMIT THE EXPOSED EARTHEN AREAS AND MINIMIZE THE EFFECT OF EARTH DISTURBANCE ACTIVITIES ON SOIL EROSION. THE AREA OF DISTURBANCE SHALL BE LIMITED TO A MAXIMUM OF 5 ACRES UNLESS OTHERWISE APPROVED BY THE ENGINEER.
- 3. RESTRICT DISTURBANCE TO UNDER 5 ACRES AT ANY ONE GIVEN TIME WITHOUT WRITTEN APPROVAL FROM THE NYS DEPARTMENT OF ENVIRONMENTAL CONSERVATION. UTILIZE TEMPORARY STABILIZATION TO REMAIN UNDER 5 ACRES OF ACTIVE DISTURBANCE AT ANY ONE GIVEN TIME.
- 4. ALL SEDIMENTATION BARRIERS AND OTHER TEMPORARY OR PERMANENT MEASURES SHALL BE IN PLACE PRIOR TO THE START OF CONSTRUCTION. PLANS SHOW THE SUGGESTED MINIMUM MEASURES REQUIRED.
- 5. REMOVAL OF ALL TEMPORARY EROSION AND SEDIMENTATION CONTROL MEASURES SHALL BE COMPLETED AT THE APPROVAL OF THE OWNER AND ENGINEER. THE COST OF REMOVING THESE MEASURES SHALL ALSO BE INCLUDED IN THE BID PRICE.
- 6. FOR THE DURATION OF THE PROJECT, THE CONTRACTOR SHALL PROTECT ALL ON-SITE, ADJACENT AND/OR DOWNSTREAM STORM/SANITARY SEWERS, AND/OR OTHER WATER COURSES FROM CONTAMINATION BY WATER BORNE SILTS, SEDIMENTS, FUELS, SOLVENTS, LUBRICANTS OR OTHER POLLUTANTS ORIGINATING FROM ANY WORK DONE ON, OR IN SUPPORT OF THIS PROJECT.
- 7. DURING CONSTRUCTION NO WET OR FRESH CONCRETE OR LEACHATE SHALL BE ALLOWED TO ESCAPE INTO STORM/SANITARY SEWERS, DITCHES OR OTHER WATERS OF NEW YORK STATE, NOR SHALL WASHINGS FROM CONCRETE TRUCKS, MIXERS OR OTHER DEVICES BE ALLOWED TO ENTER ANY STORM/SANITARY SEWERS, DITCHES, RIVERS, OR
- 8. ALL EXCAVATED OR IMPORTED EARTHEN STOCKPILES SHALL BE SUITABLY STABILIZED AND PROTECTED BY SILT FENCE SO THAT IT CANNOT REASONABLY ENTER ANY WATER BODY, OR STORM OR SANITARY SEWER.
- 9. ALL METHODS AND EQUIPMENT PROPOSED BY THE CONTRACTOR TO ACCOMPLISH THE WORK FOR EROSION AND POLLUTION CONTROL SHALL BE SUBJECT TO APPROVAL OF THE ENGINEER.
- 10. THE CONTRACTOR SHALL BE REQUIRED TO TREAT TRAVELED AREAS TO CONTROL DUST. WATER SHALL BE APPLIED TO SUCH TRAVELED AREAS AS THE ARCHITECT/ENGINEER OR OWNER'S DESIGNATED REPRESENTATIVE MAY DESIGNATE. THE NUMBER OF APPLICATIONS AND THE AMOUNT OF WATER SHALL BE BASED UPON FIELD AND WEATHER CONDITIONS.
- 11. ALL AREAS OF SOIL DISTURBANCE RESULTING FROM THIS PROJECT WHICH WILL NOT BE SUBJECT TO FURTHER EARTHWORK OR CONSTRUCTION ACTIVITIES SHALL BE PERMANENTLY SEEDED TO ESTABLISH GRASS, AND MULCHED WITH HAY OR STRAW WITHIN ONE WEEK OF FINAL DISTURBANCE. MULCH SHALL BE MAINTAINED UNTIL A SUITABLE VEGETATIVE COVER IS ESTABLISHED.
- 12. CONTRACTOR STAGING AREAS AND CONSTRUCTION ENTRANCE LOCATIONS SHALL BE COORDINATED WITH THE OWNER PRIOR TO START OF CONSTRUCTION. STABILIZED CONSTRUCTION ENTRANCE(S), AS SHOWN ON THE PLANS SHALL BE PROVIDED. ALL DISTURBED AREAS SHALL BE RESTORED.
- 13. ALL CATCH BASINS/DRAINAGE INLETS SHALL HAVE STONED INLET PROTECTION AROUND THEM AND GEOTEXTILE FABRIC OVER THE GRATE TO PREVENT SEDIMENTATION FROM ENTERING THE STORM SYSTEM.
- 14. TILL ALL COMPACTED SOILS LOCATED IN LAWN AREAS TO RESTORE THE ORIGINAL PROPERTIES OF THE SOIL PRIOR TO SEEDING.
- 15. STABILIZE DENUDED AREAS AND STOCKPILES WITHIN 7 DAYS OF LAST CONSTRUCTION ACTIVITY IN EACH AREA.
- 16. UPON COMPLETION OF THE PROJECT THE SOIL UNDERNEATH THE CONSTRUCTION STAGING AREA SHALL BE DISKED AND RESEEDED TO A DEPTH OF AT LEAST 6" BELOW EXISTING GRADE TO HELP REESTABLISH VEGETATIVE GROWTH.
- 17. CONTRACTOR TO PROVIDE 3-4 STAKEOUT LATHES DELINEATING THE WETLAND IN RELATION TO THE ORANGE CONSTRUCTION FENCE.
- 18. CONTRACTOR SHALL PROTECT VEGETATION SCHEDULED TO REMAIN WITH ORANGE CONSTRUCTION FENCING.
- 19. ALL PROPOSED 3:1 (H:V) SIDE SLOPES TO BE PERMANENTLY STABILIZED WITH ROLLED EROSION CONTROL PRODUCT PER THE DETAILS ON THIS PLAN.
- 20. TEMPORARY STONE CHECK DAMS SHALL BE INSTALLED EVERY 2 VERTICAL FOOT WITHIN THE LIMITS OF THE PROPOSED CONVEYANCE SWALE. TEMPORARY CHECK DAMS SHALL
- 21. PROPOSED LEVEL SPREADERS SHALL BE PROTECTED FROM CONSTRUCTION ACTIVITIES AND SILT ACCUMULATION WITH SILT SOCK AND/OR GEOTEXTILE FABRIC.

BE REMOVED ONCE THE SITE HAS REACHED 80% UNIFORM VEGETATIVE GROWTH.

22. THIS PROJECT IS LOCATED IN AN AGRICULTURAL DISTRIC AND SHALL ABIDE BY GUIDELINES FOR SOLAR ENERGY PROJECTS - CONSTRUCTION MITIGATION FOR AGRICULTURAL LANDS PREPARED BY THE NEW YORK STATE DEPARTMENT OF AGRICULTURE AND MARKETS (NYSDAM), DATED 10/18/2019.

#### LEGEND

#### **EXISTING PROPOSED** DESCRIPTION WETLAND \_\_\_\_\_...\_ WETLAND BUFFER TREE REMOVAL **DECIDUOUS TREE** CONIFEROUS TREE ASPHALT ACCESS ROAD PERVIOUS GRAVEL ACCESS ROAD POST-DRIVEN FENCE \_\_\_\_ BALLASTED FENCE TREE/VEGETATION LIMIT \_\_\_\_\_ — - — P — - — — – — R — — PROPERTY LINE \_\_\_\_\_ ---- SETBACK LINE RIGHT-OF-WAY <del>-</del>O-UTILITY POLE UNDERGROUND ELECTRIC —— Е ——— Е —— OVERHEAD ELECTRIC -----0E-----0E-----\_\_\_\_\_ ST \_\_\_\_\_ ST \_\_\_\_ STORM LINE ————— 510 ——— MAJOR CONTOUR ---<del>5</del>09----MINOR CONTOUR \_\_\_\_ FLOW DIRECTION \_\_\_\_ ◆ ◆ EROSION FENCE CONSTRUCTION FENCE SILT SOCK INLET PROTECTION LEVEL SPREADER CONCRETE WASHOUT STABILIZED CONSTRUCTION ENTRANCE (TEMPORARY) TOPSOIL STOCKPILES


### SCHEDULE OF CONSTRUCTION ACTIVITIES

- SCHEDULE A PRE-CONSTRUCTION MEETING WITH TOWN OFFICIALS, OWNER, EMERGENCY SERVICES, UTILITY & OTHER AGENCIES IN ATTENDANCE.
- 2. SUBMIT EROSION CONTROL MEASURES AND SEQUENCING FOR REVIEW AND APPROVAL BY THE QUALIFIED INSPECTOR.
- PROJECT BENCHMARK / CONTROL 3. STAKEOUT AND FLAG THE LIMITS OF ON-SITE WETLANDS.
  - 4. INSTALL STABILIZED CONSTRUCTION ENTRANCE.
  - 5. INSTALL PERIMETER SEDIMENT CONTROLS, SUCH AS SEDIMENT COMPOST FILTER SOCK.
  - 6. INSTALL TEMPORARY CONSTRUCTION MEASURE SUCH AS CONSTRUCTION ROAD, LAYDOWN AREA, CONSTRUCTION AREA, DESIGNATED TOPSOIL STOCKPILE AREA, STAGING AREA FENCING. ETC.
  - 7. PROTECT EXISTING VEGETATION AND OTHER ENVIRONMENTAL FEATURES TO BE PRESERVED WITH ORANGE CONSTRUCTION FENCE OR TREE PROTECTION.
  - 8. CLEAR AND GRUB BRUSH, SHRUBS, AND OTHER DEBRIS WITHIN DESIGNATED AREAS.
  - 9. INSPECT, CLEAN, AND MAINTAIN EROSION CONTROL MEASURES AS NECESSARY AND AS ORDERED BY THE QUALIFIED INSPECTOR. SWEEP PUBLIC OR PRIVATE ROADWAYS, DRIVES AND PARKING AREAS AS NECESSARY TO MAINTAIN CLEAN FROM DEBRIS. RELOCATED AND RESET EROSION CONTROL MEASURES AND CONSTRUCTION FENCING AS REQUIRED TO COMPLETE WORK. ALL APPROPRIATE EROSION AND SEDIMENT CONTROL MEASURES SHALL BE IN PLACE AND FUNCTIONAL BEFORE COMMENCEMENT OF CONSTRUCTION OF ANY SEGMENT OF THE PROJECT THAT REQUIRES SUCH MEASURES.
  - 10. STABILIZE DISTURBED AREAS AND STOCKPILES WITHIN 14 DAYS OF LAST CONSTRUCTION ACTIVITY IN EACH AREA. (7 DAYS IF GREATER THAN 5 ACRES DISTURBED).
  - 11. INSTALL UTILITES. EXCESS MATERIALS NOT BACKFILLED IN UTILITY TRENCHES SHALL BE REMOVED FROM THE SITE OR SPOILED IN AREAS APPROVED BY THE OWNER. EROSION CONTROL MEASURES ARE NOT REQUIRED AROUND SOILS (EARTHEN MATERIALS) EXCAVATED, SIDE CAST AND BACKFILLED INTO THE TRENCH WITHIN THE SAME DAY.
  - 12. DEWATER EXCAVATIONS AS NECESSARY. PUMPED WATER SHALL BE TREATED TO REMOVE SEDIMENT PRIOR TO DISCHARGE.
  - 13. RESTORE TO EXISTING GRADE AS TRENCH BACKFILLING PROGRESSING. MAINTAIN PROPER SITE DRAINAGE TO PROTECT WORK AREA, ADJACENT PROPERTIES, SWALES, AND OTHER WATERCOURSES.
  - 14. BOX OUT AREAS FOR PERVIOUS ACCESS ROADS AND EQUIPMENT PADS. AS UTILITY REPLACEMENTS ARE COMPLETE, PREPARE THE SUBGRADE AS REQUIRED.
  - 15. INSTALL CONCRETE WASHOUT AREA. NO WET OR FRESH CONCRETE, WASHINGS FROM CONCRETE TRUCKS, MIXERS, OR OTHER DEVICES, OR CONCRETE LEACHATE SHALL BE ALLOWED TO ESCAPE INTO ANY WETLANDS OR WATERS.
  - 16. INSTALL CONCRETE ELECTRICAL EQUIPMENT PADS AND THE APPROPRIATE STORMWATER MANAGEMENT FACILITIES.
  - 17. REMOVE THE TEMPORARY GRAVEL CONSTRUCTION ACCESS ROAD AND PREPARE THE SUBGRADE AS REQUIRED.
  - 18. INSTALL THE DEC APPROVED LIMITED USE PERVIOUS GRAVEL ACCESS ROAD ONCE ALL AREAS SUBJECT TO RUNOFF ONTO THE PERVIOUS ACCESS ROAD HAVE ACHIEVED FINAL STABILIZATION.
  - 19. INSTALL PERMANENT SEEDING, FERTILIZER, AND MULCH.
  - 20. COMPLETE GRADING IF REQUIRED, REAPPLY TOPSOIL, INSTALL PERMANENT SEEDING, FERTILIZER, AND MULCH.
  - 21. CAPTURE, REMOVE, AND DISPOSE OF ACCUMULATED SILT OR SEDIMENT FROM SILT FENCE, CHECK DAMS, INLET PROTECTION, AND SEDIMENT BASINS.
  - 22. CLEAN THE SITE OF ALL INCIDENTAL CONSTRUCTION MATERIALS THAT ARE NOT INCORPORATED INTO THE WORK, AND PROPERLY DISPOSE OFFSITE.
  - 23. SEED, MULCH, AND FERTILIZE TO ESTABLISH VEGETATION AT DISTURBED AREAS NOT DESIGNATED FOR PAVEMENT OR OTHER SURFACES. WHERE SEED DOES NOT GERMINATE OR WHERE WASHOUT, EROSION, RUTTING, OR OTHER DAMAGE OCCURS, REPAIR DAMAGE, RE-SEED AND RE-FERTILIZE AS NECESSARY TO ACHIEVE 80% GERMINATION OVER 100% OF THE SITE.
  - 24. REMOVE ALL TEMPORARY EROSION CONTROL PRACTICES UPON APPROVAL OF FINAL STABILIZATION BY THE QUALIFIED INSPECTOR.



300 State Street, Suite 201 Rochester, NY 14614 585-454-6110

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



#### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

2	7/14/2025	REVISED PER TOWN & USACE COMMENTS
1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		

PROJECT NUMBER:

2231877

DRAWN BY:

MSB

REVIEWED BY:

JJP

ISSUED FOR:

PERMIT

NOVEMBER 2023


GENERAL NOTES AND

**LEGEND** 

DRAWING NUMBER:


DATE:

DRAWING NAME:





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

1 11/1/2 NO: DATE Revisions		REVISED LANDSCAPING PLAN DESCRIPTION:
-	E:	DESCRIPTION:
Revisions		


PERMIT

NOVEMBER 2023

DRAWING NAME:

### **EXISTING CONDITION AND DEMOLITION PLAN**

DRAWING NUMBER:





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

## NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020


2	7/14/2025	REVISED PER TOWN & USACE COMMENTS
1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		

2231877 PERMIT

NOVEMBER 2023

DRAWING NAME:


**OVERALL SITE AND UTILITY PLAN** 





300 State Street, Suite 201 Rochester, NY 14614

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

## NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		
PROJECT	NUMBER:	

2231877 MSB REVIEWED BY: PERMIT

NOVEMBER 2023

DRAWING NAME:

SITE AND UTILITY PLAN

#### LANDSCAPING NOTES

- ALL PLANTS SHALL MEET OR EXCEED THE MINIMUM REQUIREMENTS AS NOTED IN THE LATEST EDITION OF AMERICAN STANDARD FOR NURSERY STOCK BY AMERICAN ASSOCIATION OF NURSERYMEN, ANSI Z60.1.
- REPLACE, IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS, ALL PLANTS THAT ARE MISSING, DEAD, OR DO NOT DEVELOP FROM PLANTING STOCK, OR AS DETERMINED BY THE CLIENT ARE IN UNHEALTHY OR UNSIGHTLY CONDITION, AND HAVE LOST THEIR NATURAL SHAPE DUE TO DEAD BRANCHES OR OTHER CAUSES DUE TO THE CONTRACTORS NEGLIGENCE, CONTRACTOR SHALL BEAR THE COST OF COMPLETE REPLACEMENT(S), IN CASE OF ANY QUESTIONS REGARDING THE CONDITION AND SATISFACTORY ESTABLISHMENT OF A REJECTED PLANT, THE LANDSCAPE ARCHITECT'S DECISION IS FINAL. PROVIDE A GUARANTEE FOR ALL REPLACEMENT PLANTS FOR AT LEAST ONE FULL GROWING SEASON.
- REMOVE AND IMMEDIATELY REPLACE ALL PLANTS, AS DETERMINED BY THE CLIENT TO BE UNSATISFACTORY DURING THE INITIAL PLANTING
- SHRUBS SHALL MEET THE REQUIREMENTS FOR HEIGHT INDICATED IN THE PLANT LIST. THE MEASUREMENTS FOR HEIGHT SHALL BE TAKEN FROM THE GROUND LEVEL TO THE AVERAGE HEIGHT OF THE TOP BRANCHES OF THE PLANT, AND NOT THE LONGEST BRANCH. SINGLE STEMMED OR THIN PLANTS WILL NOT BE ACCEPTED. SIDE BRANCHES SHALL BE GENEROUS, WELL TWIGGED, AND THE PLANT AS A WHOLE WELL SEATED IN THE GROUND. PLANTS SHALL BE IN A MOIST, VIGOROUS CONDITION, FREE FROM DEAD WOOD, BRUISES, OR OTHER ROOT OR BRANCH INJURIES.
- PLANTED AREAS WILL BE INSPECTED AT COMPLETION OF INSTALLATION AND ACCEPTED SUBJECT TO COMPLIANCE WITH SPECIFIED MATERIALS AND INSTALLATION REQUIREMENTS. INSPECTION TO DETERMINE FINAL ACCEPTANCE OF PLANTED AREAS WILL BE MADE BY THE CLIENT UPON CONTRACTORS REQUEST, PROVIDE NOTIFICATION AT LEAST 10 WORKING DAYS BEFORE REQUESTED INSPECTION DATE, PLANTED AREAS WILL BE ACCEPTED PROVIDED ALL MATERIALS ARE ALIVE AND IN A HEALTHY, VIGOROUS CONDITION. UPON FINAL ACCEPTANCE, THE OWNER WILL ASSUME MAINTENANCE.
- A ONE YEAR GUARANTEE SHALL BE PROVIDED FOR ALL NEW AND RELOCATED PLANT MATERIALS FROM DATE OF FINAL ACCEPTANCE TO THE OWNER.
- THE CONTRACTOR SHALL BE RESPONSIBLE FOR HIS OWN QUANTITY TAKEOFF.
- THE CONTRACTOR SHALL PERFORM A ROUGH FIELD STAKE OUT OF ALL PLANT MATERIAL AND SHRUB BEDS. CONTACT THE ENGINEER FOR INSPECTION AND APPROVAL, LOCATIONS SHOWN ON THE PLAN CONVEY DESIGN INTENT ONLY. ACTUAL LOCATIONS WILL BE AS DIRECTED BY THE ENGINEER AT THE TIME OF INSTALLATION.
- NAMES OF WOODY PLANT MATERIAL MUST COMPLY WITH "STANDARDIZED PLANT NAMES" AS ADOPTED BY THE LATEST EDITION OF THE AMERICAN JOINT COMMITTEE OF HORTICULTURAL NOMENCLATURE. PROVIDE STOCK TRUE TO BOTANICAL NAME AND LEGIBLY TAGGED.
- SHOULD LOCATION OF TREES BE WITHIN 5' OF UNDERGROUND UTILITIES, RELOCATE SAID TREES TO MIN. OF 5' FROM ROOT BALL TO UTILITIES.

GENESEE COMMUNITY COLLEGE

FOUNDATION HOUSING SERVICES, INC.

S.B.L. 01-02-117.2 INSTR. NO. DE2019-1782

► PROPOSED NY CDG GENESEE 6 LLC

DELINEATED USACE -

PEM WETLAND BOUNDARY

PROPERTY LINE —

PROPOSED NY CDG GENESEE 5 LLC

— PROPOSED NY CDG GENESEE 5 LLC

DE OE OE OE OE

DELINEATED USACE UNCLASSIFIED EPHEMERAL DITCH BOUNDARY

DELINEATED NYSDEC/USACE -

INTERMITTENT STREAM BOUNDARY

74 ——— 74 ——— 7e

- 200' SETBACK LINE

POINT OF INTERCONNECTION

UTILITY POLE LINE UP (TYP)

- PROPOSED NY CDG GENESEE 6 LLC

POINT OF INTERCONNECTION

N 43° 00' 53.32" W 78° 07' 59.73"

- 11. SHOULD LOCATIONS OF TREES OF LARGER SPECIES BE WITHIN 20' OF OVERHEAD WIRES, RELOCATE SAID TREES TO MIN. OF 20' TO WIRES.
- 12. STAKE AND WRAP TREES IMMEDIATELY AFTER PLANTING. STAKES AND WRAPPING ARE TO BE REMOVED BY THE CONTRACTOR AT THE END OF THE GUARANTEE PERIOD.
- 13. MULCH ALL TREES AND SHRUB BEDS WITH 3" DOUBLE GROUND HARDWOOD BAR, COLOR: DARK BROWN. 'RIVER STONE' SURFACE SHALL BE SMOOTH, WASHED, GRADED GRAVEL, 1" TO 2" SIZE. PLACE ON FIBER MAT WEED BARRIER: MIRAFI 100X OR EQUAL.
- 14. PLANTING BACK FILL MIXTURE: 4 PARTS TOP SOIL; 1 PART PEAT MOSS; 1/2 PART WELL ROTTED MANURE; 10 LBS, 5-10-5 PLANTING FERTILIZER

THOROUGHLY MIXED PER CUBIC YARD.

LLC CONCRETE ELECTRICA EQUIPMENT PAD (TY

PROPOSED TRACKING SOLAR PANELS (TYP) -

PROPOSED LANDSCAPE SCREENING (TYP)

REFER TO THE LANDSCAPING PLAN —

PROPOSED 20' WIDE LIMITED USE PERVIOUS GRAVEL ACCESS ROAD (TYP) -

- 15. TOPSOIL SHALL BE FURNISHED FROM THE STOCKPILED ON-SITE MATERIAL. ON-SITE MATERIAL IS TO BE MECHANICALLY SCREENED, ANYTHING LARGER THAN 0.5" SHALL BE REMOVED AND DISPOSED. IF AN INSUFFICIENT QUANTITY EXISTS, FURNISH FROM OFF-SITE SOURCES IN QUANTITIES SUFFICIENT TO COMPLETE THE REQUIREMENTS AS SPECIFIED. TOPSOIL SHALL BE NATURAL, FRIABLE, FERTILE SOIL, CHARACTERISTIC OF PRODUCTIVE SOIL IN THE VICINITY, FREE FROM STONES, CLAY LUMPS, ROOTS AND OTHER FOREIGN MATTER WITH AN ACIDITY BETWEEN 6.0 AND 6.8 ph. PROPOSED TOPSOIL MATERIAL FROM OFF-SITE SOURCES SHALL BE MECHANICALLY SCREENED SUBJECT TO APPROVAL BY THE ENGINEER.
- 16. EXISTING TOPSOIL ON SITE CAN BE USED IF IT MEETS OR EXCEEDS NYSDOT ITEM 610.1401 'RE-USE OF TOPSOIL ON SITE'. THE EXISTING SOIL SHOULD BE TILLED TO THE FULL DEPTH OF TOPSOIL, A MINIMUM OF 8" DEPTH AND A MAXIMUM OF 12" USING A CAT-MOUNTED RIPPER. TRACTOR MOUNTED DISC. OR TILLER. THE AREA IS TO BE ROCK-PICKED UNTIL UPLIFTED STONE/ROCK MATERIALS OF 2 INCHES AND LARGER SIZE ARE REMOVED TO A 4" DEPTH AND CLEANED OFF SITE. TOPSOIL SHALL BE TREATED TO FLIMINATE INVASIVE SPECIES AND WEEDS PER SECTION 610-3.01. WEED REMOVAL, THE APPLICATION OF FERTILIZER, SOIL AMENDMENTS, SEED, STRAW, CELLULOSE FIBER, TACKIFIER, AND INOCULENT AS REQUIRED PER SECTION 610-3.03, 'TURF ESTABLISHMENT' AND PER ANY ADDITIONAL NOTATIONS OR SPECIFICATIONS ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN TURF ESTABLISHMENT AREAS INCLUDING WATERING, MOWING TO A 5" AVERAGE HEIGHT, FERTILIZER AND OTHER AMENDMENTS AS MAY BE REQUIRED FOR
- 17. IF THE ONSITE EXISTING CONDITIONS ARE NOT ABLE TO MEET NYSDOT ITEM 610.1401 THEN MECHANICALLY SCREENED TOPSOIL SHALL BE IMPORTED AND SPREAD ON ALL AREAS TO BE SEEDED TO A MINIMUM DEPTH OF 6". IMPORTED TOPSOIL SHALL MEET THE REQUIREMENTS OF ITEM 610.1402 -ROADSIDE. ESTABLISHMENT OF TURF SHALL MEET THE REQUIREMENTS OF ITEM 610.1601, TURF ESTABLISHMENT -ROADSIDE. TOPSOIL SHALL INCLUDE THE SPREADING OF TOPSOIL PER SECTION 610-3.01, THE APPLICATION OF FERTILIZER, SOIL AMENDMENTS, SEED, STRAW, CELLULOSE FIBER, TACKIFIER, AND INOCULENT AS REQUIRED PER SECTION 610-3.03, 'TURF ESTABLISHMENT' AND PER ANY ADDITIONAL NOTATIONS OR SPECIFICATIONS ON THE PLANS. THE CONTRACTOR SHALL MAINTAIN TURF ESTABLISHMENT AREAS INCLUDING WATERING, MOWING TO A 5" AVERAGE HEIGHT, FERTILIZER AND OTHER AMENDMENTS AS MAY BE REQUIRED FOR THE HEALTHY ESTABLISHMENT OF TURF.
- 18. IF THE ONSITE EXISTING CONDITIONS ARE NOT ABLE TO MEET NYSDOT ITEM 610.1401 THEN A MINIMUM OF 6" OF MECHANICALLY SCREENED TOPSOIL SHALL BE PROVIDED ON ALL AREAS TO BE SEEDED. THE IMPORTED SOIL SHOULD BE TILLED TO A DEPTH OF AT LEAST 12 INCHES USING A CAT-MOUNTED

- RIPPER, TRACTOR MOUNTED DISC, OR TILLER. THE AREA IS TO BE ROCK-PICKED UNTIL UPLIFTED STONE/ROCK MATERIALS OF 1/2 INCHES AND LARGER SIZE ARE CLEANED OFF SITE. FERTILIZER, SEED, AND STRAW CAN THEN BE APPLIED.
- 19. LAWN SEED MIXTURE- APPLY TO ALL AREAS NOT PAVED, PLANTED, DESIGNATED TO REMAIN NATURAL OR OTHERWISE SEEDED. MIX SHALL CONSIST OF

	% WEIGHT	% PURITY	% GERMINATION	
EYSTONE PERRENIAL RYEGRASS	25	85	85	
HARISMATIC PERRENIAL RYEGRASS	25	85	85	
INDY LOU CREEPING RED FESCUE	20	85	80	

SEEDING RATE: 200 LBS. PER ACRE FERTILIZER: 18:24:3 GRANULAR RATE: 1,000 LBS. PER ACRE

MULCH ALL SEEDED AREAS WITH APPROVED STRAW AT A RATE OF 4,000 LBS. PER ACRE.

20. POLLINATOR/WILDFLOWER/LOW GROW MAINTENANCE SEED MIXTURE- APPLY TO ALL DESIGNATED AREAS ONLY. THE MIXTURE SHALL CONSIST OF THE

35% FIREFLY HARD FESCUE 20% INTRIGUE CHEWINGS FESCUE

COMMON KENTUCKY BLUEGRASS

20% EUREKA II HARD FESCUE 10% MINOTAUR HARD FESCUE 15% XERCES NORTHEASTERN POLLINATOR MIX. ERNST-179, ERNST SEEDS, MEADVILLE, PA

MICHELLE WOOD

D. 505 PG. 208

S.B.L. 01-02-115

SEEDING RATE: 50 LBS. PER ACRE

- FERTILIZER: 28:4:12 GRANULAR RATE: 1,000 LBS. PER ACRE MULCH ALL SEEDED AREAS WITH APPROVED STRAW AT A RATE OF 4,000 LBS. PER ACRE.
- 21. LANDSCAPE MATERIALS SHALL BE INSTALLED BY LOCAL COMPANIES FAMILIAR WITH THE CONDITIONS IN THIS AREA THAT EMPLOY NYS CERTIFIED
- 22. STAKE PLANTS AS INDICATED OR AS APPROVED IN THE FIELD. IF OBSTRUCTIONS ARE ENCOUNTERED THAT ARE NOT SHOWN ON THE DRAWINGS, DO NOT PROCEED PLANTING OPERATIONS UNTIL ALTERNATIVE PLANT LOCATIONS HAVE BEEN SELECTED.
- 23. MAINTAIN PLANTS UNTIL COMPLETION AND FINAL ACCEPTANCE OF THE ENTIRE PROJECT. MAINTENANCE SHALL INCLUDE PRUNING, CULTIVATING,

EDGING, REMULCHING, FERTILIZING, WEEDING, WATERING AS REQUIRED FOR HEALTHY GROWTH, AND APPLICATION OF APPROPRIATE INSECTICIDES AND FUNGICIDES NECESSARY TO MAINTAIN PLANTS FREE OF INSECT AND DISEASE. RESET SETTLED PLANTS TO PROPER GRADE AND POSITION. RESTORE PLANTING SAUCER AND REMOVE DEAD MATERIAL. TIGHTEN AND REPAIR GUIDE WIRES AND DEFICIENCIES WITHIN THE FIRST 24 HOURS OF INITIAL PLANTING, AND NOT LESS THAN TWICE PER WEEK UNTIL FINAL ACCEPTANCE.

24. FINAL LOCATION OF TREES AND OTHER LANDSCAPING SHALL BE DETERMINED IN THE FIELD BASED ON UTILITY STAKEOUT. LANDSCAPING SHALL BE PLACED SO AS NOT TO CONFLICT WITH UTLITIES.

#### **QUANTITIES TABLE**

#### PLANT SCHEDULE

		•	EMIT GOILEGGEE			
KEY	QUANT.	SCIENTIFIC NAME	COMMON NAME	INSTALLED SIZE	MATURE SIZE	SPACING
TS	111	Thuja plicata x standishii	THUJA GREEN GIANT	7-8' Ht.	40' Ht./ 15' Sp.	As Shown
TM	90	Taxus x media 'Hicksii'	HICKSII YEW	4' Ht	10-14' Ht./ 5' Sp.	As Shown

POLLINATOR/WILDFLOWER SEED MIX

mum ympummu, a,

#### LANDSCAPE MAINTENANCE AFTER FINAL ACCEPTANCE

- 1. BUFFER PLANTINGS AND THE POLLINATOR/WILDFLOWER MIX SHALL BE INSPECTED AND MAINTAINED MONTHLY DURING THE FIRST GROWING SEASON, AND QUARTERLY AFTER THAT.
- MAINTENANCE INCLUDES REMOVING WEEDS AND REPLACING ANY PLANT THAT DIES WITH THE SAME SPECIES AND SIZE AS ORIGINALLY INSTALLED.

Manual Ma

THE POLLINATOR MIX SHALL BE CUT ANNUALLY IN THE SPRING, AND RESEEDED AS NECESSARY.

±32 AC

4. INSPECTION AND MAINTENANCE SHALL BE PERFORMED BY A QUALIFIED LOCAL LANDSCAPE MAINTENANCE COMPANY.

DELINEATED

EXISTING TREELINE

NYSDEC/USACE INTERMITTENT

STREAM BOUNDARY

It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

300 State Street, Suite 201

Rochester, NY 14614

585-454-6110

labellapc.com

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

	1/11/2020	TIEVIOLD I EIT TOVITA A COMOL COMMENTO
1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		

2 7/14/2025 REVISED PER TOWN & USACE COMMENTS

PROJECT NUMBER: 2231877 DRAWN BY:


REVIEWED BY


PERMIT DATE: **NOVEMBER 2023** 

DRAWING NAME:

ISSUED FOR:

LANDSCAPE PLAN








300 State Street, Suite 201 Rochester, NY 14614

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

1	11/1/2024	REVISED LANDSCAPING PLAN	
NO:	DATE:	DESCRIPTION:	
Revisions			
PROJECT NUMBER:			
		2231877	

REVIEWED BY PERMIT

**NOVEMBER 2023** 

DRAWING NAME:

**EROSION AND SEDIMENT CONTROL PLAN** 





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

## **NY CDG GENESEE 6, LLC**

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

2	7/14/2025	REVISED PER TOWN & USACE COMMENTS
1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		

PROJECT NUMBER:

2231877

DRAWN BY:

MSB

REVIEWED BY:

JJP

PERMIT


DATE:

NOVEMBER 2023

DRAWING NAME:

**OVERALL GRADING PLAN** 

DRAWING NUMBER:





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

## NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



#### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

NO:		
	DATE:	DESCRIPTION:
Revisions		
PROJECT N	IUMBER:	2231877

2 7/14/2025 REVISED PER TOWN & USACE COMMENTS

DRAWN BY:

MSB

REVIEWED BY:

JJP

ISSUED FOR:


DATE: NOVEMBER 2023

NUVEWBER 2023

DRAWING NAME:

**GRADING PLAN** 

DRAWING NUMBER:



**GRASS FILTER STRIP** C501 / N.T.S. **WOVEN WIRE FENCE (MIN. 14 1/2 GAUGE** W/ MAX. 6" MESH SPACING WITH FILTER -- 36" MIN. FENCE POSTS, DRIVEN 10' MAX. C. TO C. MIN. 16" INTO

NOTES:

LENGTH VARIES, SEE PLANS. THE


ENTIRE FILTER STRIP AREA MUST

OF 12% WITH THE UPSLOPE AREA

NO DEVELOPMENT IS ALLOWED ON

FILTER STRIP AREA.


**RESULT IN A COMBINED MAX SLOPE** 



SECTION VIEW

- WOVEN WIRE FENCE TO BE FASTENED SECURELY TO FENCE POSTS WITH WIRE TIES OR STAPLES. POSTS SHALL BE STEEL EITHER "T" OR "U" TYPE OR HARDWOOD. 2. FILTER CLOTH TO BE FASTENED SECURELY TO WOVEN WIRE FENCE WITH TIES SPACED EVERY 24" AT TOP AND MID SECTION.
- FENCE SHALL BE WOVEN WIRE, 6" MAXIMUM MESH OPENING.
- WHEN TWO SECTIONS OF FILTER CLOTH ADJOIN EACH OTHER THEY SHALL BE OVER-LAPPED BY SIX INCHES AND FOLDED.
- FILTER CLOTH SHALL BE EITHER FILTER X, MIRAFI 100X, STABLINKA 140N, OR APPROVED EQUAL. PREFABRICATED UNITS SHALL BE GEOFAB, ENVIROFENCE, OR APPROVED EQUAL.
- MAINTENANCE SHALL BE PERFORMED AS NEEDED AND MATERIAL REMOVED WHEN "BULGES" DEVELOP IN THE SILT FENCE. SILT FENCE

### C501 / NYS DEC DETAIL: SILT FENCE



- 1. SOCK FABRIC SHALL MEET STANDARDS OF TABLE 5.1. COMPOST SHALL MEET THE
- STANDARDS LISTED ON OF TABLE 5.2. 2. COMPOST FILTER SOCK SHALL BE PLACED AT EXISTING LEVEL GRADE. BOTH ENDS OF THE SOCK SHALL BE EXTENDED AT LEAST 8 FEET UP SLOPE AT 45 DEGREES TO THE MAIN SOCK ALIGNMENT (FIGURE 5.2). MAXIMUM SLOPE LENGTH ABOVE ANY SOCK SHALI NOT EXCEED THAT SHOWN ON FIGURE X.X. STAKES MAY BE INSTALLED IMMEDIATELY DOWNSLOPE OF THE SOCK IF SO SPECIFIED BY THE MANUFACTURER.
- TRAFFIC SHALL NOT BE PERMITTED TO CROSS FILTER SOCKS. 4. ACCUMULATED SEDIMENT SHALL BE REMOVED WHEN IT REACHES HALF THE ABOVEGROUND HEIGHT OF THE SOCK AND DISPOSED IN THE MANNER DESCRIBED ELSEWHERE IN THE PLAN.
- 5. SOCKS SHALL BE INSPECTED WEEKLY AND AFTER EACH RUNOFF EVENT. DAMAGED SOCKS SHALL BE REPAIRED ACCORDING TO MANUFACTURER'S SPECIFICATIONS OR REPLACED WITHIN 24 HOURS OF INSPECTION.
- 6. BIODEGRADABLE FILTER SOCKS SHALL BE REPLACED AFTER 6 MONTHS; PHOTODEGRADABLE SOCKS AFTER 1 YEAR. POLYPROPYLENE SOCKS SHALL BE REPLACED ACCORDING TO MANUFACTURER'S RECOMMENDATIONS.
- UPON STABILIZATION OF THE AREA TRIBUTART TO THE SOCKS, STAKES SHALL BE REMOVED. THE SOCK MAY BE LEFT IN PLACE AND VEGETATED OR REMOVED. IN THE LATTER CASE, THE MESH SHALL BE CUT OPEN AND THE MULCH SPREAD AS A SOIL SUPPLEMENT.

SEE STRUCTURAL DRAWINGS FOR CONCRETE PAD DETAILS

. MIN. 6" COVEI

SECTION VIEW

PLAN VIEW

ELECTRICAL EQUIPMENT CONCRETE PAD

## COMPOST FILTER SOCK

NYS DEC DETAIL: COMPOST FILTER SOCK

GEOTEXTILE FABRIC
(MIRAFI 180N OR —

GRADE

COMPACTED SUBGRADI


(SUITABLE SOIL MATERIAL)

GRAVEL -

**EXTENTS** 

EXTENTS OF

CONCRETE PAD



### CONSTRUCTION SPECIFICATIONS

- 1. STONE SIZE USE 1-4 INCH STONE, OR RECLAIMED OR RECYCLED CONCRETE EQUIVALENT.
- 2. LENGTH NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY).
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH TWELVE (12) FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCURS. TWENTY-FOUR (24) FOOT IF SINGLE ENTRANCE TO SITE.
- 5. GEOTEXTILE WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE
- 6. SURFACE WATER ALL SURFACE WATER FLOWING OR DIVERTED TOWARD CON-STRUCTION ACCESS SHALL BE PIPED BENEATH THE ENTRANCE. IF PIPING IS
- IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED. 7. MAINTENANCE - THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY, ALL
- SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. 8. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON A AREA STABILIZED WITH STONE
- AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH

#### STABILIZED CONSTRUCTION ACCESS

NYS DEC DETAIL: STABILIZED CONSTRUCTION ACCESS

**EQUIPMENT SKID DIMENSIONS** 

1. ALL ELECTRICAL EQUIPMENT IS TO BE SITUATED ON A CONCRETE PAD AS SHOWN

2. CONCRETE STRENGTH: CLASS B CONCRETE. CONTRACTOR SHALL ALLOW 3 DAYS

CURING TIME PRIOR TO INSTALLATION OF EQUIPMENT ON CONCRETE PAD.

A CLASS 2 COATING EQUAL TO THAT SPECIFIED IN ASTM A641, TABLE 1.

5. LOCATION OF ALL ELECTRICAL EQUIPMENT AND CONCRETE PADS SHALL BE

FOOTING AS PER MANUFACTURER'S SPECIFICATIONS.

APPROVED BY THE OWNER PRIOR TO CONSTRUCTION.

EQUAL BY THE ENGINEER OF RECORD.

SKID SHOP DRAWINGS.

EMBEDMENT DEPTH OR APPROVED EQUAL.

4. ANCHOR BOLTS SHALL BE DRILLED AND SET IN FIELD AFTER INSTALLATION ON

6. COMPACTED STONE SHALL BE NYSDOT TYPE 2 CRUSHED GRAVEL OR APPROVED

7. ANCHOR BOLTS SHALL BE  $\frac{1}{2}$ " DIA. HILTI HSE ADHESIVE ANCHOR RODS WITH 4-1/2"

9. VERIFY ALL DIMENSIONS WITH THOSE ON EQUIPMENT SKID SHOP DRAWINGS AND

ADJUST ACCORDINGLY. LOCATE CHASES AND CONDUIT STUB-UPS PER EQUIPMENT

8. REINFORCEMENT BARS SHALL CONFORM TO ASTM A615, GRADE 60.

10. GROUNDING PLATE TO BE LOCATED UNDERNEATH EQUIPMENT PAD

11. GROUNDING RINGS TO BE BURIED AT EQUIPMENT PAD LOCATION

3. WELDED WIRE FABRIC SHALL CONFORM TO ASTM A185, Fy=64500 PSI, AND SHALL

BE HOT-DIPPED GALVANIZED OR EPOXY COATED AFTER FABRICATION TO PRODUCE


DIM. A (FT) | DIM. B (FT) | DIM. C (FT) | DIM. D (FT)

EQUIPMENT

MAIN EQUIPMENT PAD

**EQUIPMENT SKID NOTES:** 

ON THE SITE PLANS.




1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND STABLE. 2. MAXIMUM SLOPE OF STOCKPILE SHALL BE 1V:2H.

4. SEE SPECIFICATIONS AND DETAIL FOR INSTALLATION OF SILT FENCE.

- 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE SURROUNDED WITH SILT FENCING, THEN STABILIZED WITH VEGETATION OR COVERED.

### TEMPORARY SOIL STOCKPILE



C501 / N.T.S.

CAN BE TWO STACKED BALES OR PARTIALLY EXCAVATED TO REACH 3 FT DEPTH

#### CONSTRUCTION SPECIFICATIONS

STRUCTURE IS REMOVED.

- 1. LOCATE WASHOUT STRUCTURE A MINIMUM OF 50 FEET AWAY FROM OPEN CHANNELS, STORM DRAIN INLETS, SENSITIVE AREAS,
- WETLANDS, BUFFERS AND WATER COURSES AND AWAY FROM CONSTRUCTION TRAFFIC. SIZE WASHOUT STRUCTURE FOR VOLUME NECESSARY TO CONTAIN WASH WATER AND SOLIDS AND MAINTAIN AT LEAST 4 INCHES OF
- FREEBOARD. TYPICAL DIMENSIONS ARE 10 FEET X 10 FEET X 3 FEET DEEP. PREPARE SOIL BASE FREE OF ROCKS OR OTHER DEBRIS THAT MAY CAUSE TEARS OR HOLES IN THE LINER. FOR LINER, USE 10 MIL OR THICKER UV RESISTANT, IMPERMEABLE SHEETING, FREE OF HOLES AND TEARS OR OTHER DEFECTS THAT COMPROMISE
- IMPERMEABILITY OF THE MATERIAL PROVIDE A SIGN FOR THE WASHOUT IN CLOSE PROXIMITY TO THE FACILITY.
- KEEP CONCRETE WASHOUT STRUCTURE WATER TIGHT. REPLACE IMPERMEABLE LINER IF DAMAGED (E.G., RIPPED OR PUNCTURED). EMPTY OR REPLACE WASHOUT STRUCTURE THAT IS 75 PERCENT FULL, AND DISPOSE OF ACCUMULATED MATERIAL PROPERLY. DO NOT REUSE PLASTIC LINER. WET-VACUUM STORED LIQUIDS THAT HAVE NOT EVAPORATED AND DISPOSE OF IN AN APPROVED MANNER. PRIOR TO FORECASTED RAINSTORMS, REMOVE LIQUIDS OR COVER STRUCTURE TO PREVENT OVERFLOWS, REMOVE HARDENED SOLIDS, WHOLE OR BROKEN UP, FOR DISPOSAL OR RECYCLING. MAINTAIN RUNOFF DIVERSION AROUND EXCAVATED WASHOUT STRUCTURE UNTIL

#### CONCRETE WASHOUT AREA WITH STRAW BALES







#### TRENCH NOTES:

- ADDITIONAL MISCELLANEOUS CABLES FROM FIELD DEVICES SUCH AS TEMPERATURE TRANSMITTERS, METEOROLOGICAL STATIONS, REFERENCE MODULES, SIGNAL GROUND SHALL UTILIZE THE UNDERGROUND TRENCH SYSTEM WHERE IT IS APPLICABLE. CABLES SHALL BE INSTALLED AT LAYERS
- 2. THE TRENCH DETAIL BELOW SHOWS A FROM DC COMBINER BOXES. SPECIFIC CABLE QUANTITIES ARE SHOWN IN
- 3. TRENCHING MUST COMPLY WITH THE
- LATEST STANDARDS. BEDDING SHALL BE SAND OR ROCK-FEE FILL SCREENED TO A MAXIMUM 1/4" SIZE AS A CUSHING (FREE OF SHARP EDGE MATERIAL ROTTING WOOD OR ORGANIC MATTER THAT
- MIGHT ATTRACT INSECTS). THE CABLES SHALL BE COVERED WITH "CLEAN FILL" SAND OR SOFT EARTH, FREE FROM STONES, ROCKS OR OTHER MATERIAL
- UNTREATED NATIVE SOIL CLEAN, DRY BACKFILL CUSHION

- 1. CONDUCTORS TO BE 1000V RATED FOR DIRECT BURIIAL. MEDIUM VOLTAGE CONDUCTORS FROM PS1 TO BE RATED FOR CLASS 35KV, AND MEDIUM VOLTAGE CONDUCTORS FROM PS2 TO BE RATED FOR CLASS 15KV.
- CONDUCTORS OF THE SAME CIRCUIT TO BE NEXT TO EACH OTHER; COMBINER CIRCUITS TO BE SPACED 4.5" FROM EACH OTHER UNLESS
- POSTED OTHERWISE (HORIZONTAL/VERTICAL DIRECTIONS).
- COMMUNICATIONS TO BE BURIED 1' AWAY FROM ALL POWER CONDUCTORS. USE DIRECT BURY RATED FIBER CABLE. 4. 3" OR 4" PVC SCH80 JUMP-CONDUIT SHALL BE UTILIZED FOR ROW-TO-ROW STRING CIRCUITS WIRING.
- POWER SUPPLY CABLES TO ARC FAULT CIRCUIT INTERRUPTION CIRCUITS SHALL BE LOCATED AT A MINIMUM 1' FROM DC CIRCUITS.
- CONTRACTOR SHALL SIZE THE ROW-TO-ROW JUMPER CONDUIT FOR THE CONDUCTORS USED, WITH PVC SCHEDULE 80. A TOTAL OF 60 #10 HOMERUN CABLES CAN FIT INTO A STANDARD 4" PVC CONDUIT. CONTACT THE ENGINEER IF ADDITIONAL GUIDANCE IS REQUIRED.

#### TYPICAL TRENCH DETAILS





# AS INDICATED.

- SAMPLE NUMBER OF DC FEEDER CABLES RESPECTIVE DETAIL SECTION.
- 4. CLEAN FILL REQUIREMENTS: TRENCHING
- THAT MAY DAMAGE THE CABLE DURING BACKFILL.
- 5. THE CABLES CROSS-SECTION AND THE NUMBER SHOWN IS ONLY AN EXAMPLE. ALL CABLES SHALL BE IN ACCORDANCE WITH STANDARDS AND SHALL BE SIZED ACCORDING TO USE AND TYPE OF INSTALLATION.
- EARTH UNDISTURBED

### **CONSTRUCTION DETAILS**

1 11/1/2024

PROJECT NUMBER:

DRAWN BY:

REVIEWED BY:

ISSUED FOR:

DRAWING NAME:

DATE:

300 State Street, Suite 201

It is a violation of New York Education Law Article 145

Sec.7209, for any person, unless acting under the direction

of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered;

the altering architect, engineer, or land surveyor shall affix

to the item their seal and notation "altered by" followed by

their signature and date of such alteration, and a specific

description of the alteration.

© 2020 LaBella Associates

NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700

HOUSTON, TX 77024

**GENESEE 6 SOLAR ARRAY** 

8244 BATAVIA-STAFFORD TOWNLINE ROAD

BATAVIA, NY 14020

2 7/14/2025 REVISED PER TOWN & USACE COMMENTS

2231877

MSB

PERMIT


NOVEMBER 2023


REVISED LANDSCAPING PLAN

Rochester, NY 14614

585-454-6110

labellapc.com





# **GENESEE 5 SOLAR ARRAY**

**COMPANY LLC** 24HR EMERGENCY CONTACT NAME, PHONE, ADDRESS



PENAL LAW SECTION 140.10



INTERFERING WITH THE OPERATION OF THIS FACILITY IS IN VIOLATION OF TITLE 18. UNITED STATES CODE SECTION 1366 AND PUNISHABLE BY 10 YEARS **IMPRISONMENT AND \$50,000 FINE.** 





THESE FACILITIES ARE MONITORED BY VIDEO & **ELECTRONIC SECURITY EQUIPMENT** 

C502 N.T.S.


1. ALL SIGNS TO BE 18" x 24" IN SIZE

SIGNS SHALL BE UV RESISTANT AND IN COLOR. SIGN MATERIAL SHALL BE HDPE OR LIGHT GAGE GALVANIZED STEEL.

3. SIGNS TO BE ATTACHED TO FENCING WITH PERMANENT FASTENERS.

PERMANENT SIGNAGE

C502 N.T.S.



7' HIGH POST-DRIVEN FENCE

C502 N.T.S.

ÇLÔCK EYÊ & PAD LOCK STRETCHER BARS STRETCHER BARS X HINGE 🗧 FINISHED GRADE -ALL POSTS AND RAILS SHALL CONFORM TO: GROUP IA: (ASTM CHAIN LINK 4,000 PSI CONCRETE FOOTING (TYP.) 12"

 $-1\frac{5}{8}$ " ROUND TUBULAR

GÄLVANIZED FRAMING

4'-0"

1. ALL FABRIC SHALL BE BLACK VINYL COATED (THERMALLY FUSED AND BONDED).

2. TIES SHALL BE HOT-DIP GALVANIZED, .90 OZ. ZINC PER SQ. FT.WITH BLACK VINYL COATING


3. ALL POSTS, RAILS, AND APPURTENANCES SHALL BE HOT-DIP GALVANIZED WITH BLACK VINYL COATING IN ALL ATHLETIC FIELD INSTALLATIONS, FABRIC SHALL BE INSTALLED ON THE PLAY FIELD SIDE OF THE FRAMING.

F1043) SCHEDULE 40 STEEL PIPE, ASTM F1083 REGULAR GRADE FENCING SYSTEM IS DESIGNED TO WITHSTAND A WIND SPEED OF

105 MPH.

7' HIGH CHAIN LINK SINGLE SWING GATE

C502 N.T.S.




7' TALL 22' WIDE DOUBLE SWING GATE

C502 N.T.S.

300 State Street, Suite 201 Rochester, NY 14614 585-454-6110

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

2 7/14/2025 REVISED PER TOWN & USACE COMMENTS


1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		
PROJECT	NUMBER:	2231877
DRAWN BY: REVIEWED BY:		MSB
		JJP
ISSUED FO	OR:	PERMIT

DATE: **NOVEMBER 2023** 


**CONSTRUCTION DETAILS** 

DRAWING NUMBER:

DRAWING NAME:








TYPICAL PANEL AND RACK DIMENSIONS


503 N.T.S.





300 State Street, Suite 201 Rochester, NY 14614 585-454-6110

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### **NY CDG GENESEE 6, LLC**

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

2	7/14/2025	REVISED PER TOWN & USACE COMMENTS	
1	11/1/2024	REVISED LANDSCAPING PLAN	
NO:	DATE:	DESCRIPTION:	
Revisions			

PROJECT NUMBER:

2231877

DRAWN BY:

MSB

REVIEWED BY:

JJP

ISSUED FOR:

PERMIT

DATE:

NOVEMBER 2023

DRAWING NAME:

**CONSTRUCTION DETAILS** 

DRAWING NUMBER:

#### GENERAL NOTES:

- 1. USE OF THIS DETAIL/CRITERION IS LIMITED TO ACCESS ROADS USED ON AN OCCASIONAL BASIS ONLY (I.E. PROVIDE ACCESS FOR MOWING, EQUIPMENT REPAIR OR MAINTENANCE, ETC.).
- 2. LIMITED USE PERVIOUS ACCESS ROAD IS LIMITED TO LOW IMPACT IRREGULAR MAINTENANCE ACCESS ASSOCIATED WITH RENEWABLE ENERGY PROJECTS IN NEW YORK STATE.
- 3. REMOVE STUMPS, ROCKS AND DEBRIS AS NECESSARY. FILL VOIDS TO MATCH EXISTING NATIVE SOILS AND COMPACTION LEVEL.
- 4. REMOVED TOPSOIL MAY BE SPREAD IN ADJACENT AREAS AS DIRECTED BY THE PROJECT ENGINEER, COMPACT TO THE DEGREE OF THE NATIVE INSITU SOIL, DO NOT PLACE IN AN AREA THAT IMPEDES STORMWATER DRAINAGE.
- 5. GRADE ROADWAY, WHERE NECESSARY, TO NATIVE SOIL AND DESIRED ELEVATION. MINOR
- 6. REMOVE REFUSE SOILS AS DIRECTED BY THE PROJECT ENGINEER. DO NOT PLACE IN AN AREA
- 7. ROADWAY WIDTH TO BE DETERMINED BY CLIENT.

THAT IMPEDES STORMWATER DRAINAGE.

GRADING FOR CROSS SLOPE CUT AND FILL MAY BE REQUIRED.

- 8. THE LIMITED USE PERVIOUS ACCESS ROAD CROSS SLOPE SHALL BE 2% IN MOST CASES AND SHOULD NOT EXCEED 6%. THE LONGITUDINAL SLOPE OF THE ACCESS DRIVE SHOULD NOT
- 9. LIMITED USE PERVIOUS ACCESS ROAD IS NOT INTENDED TO BE UTILIZED FOR CONSTRUCTION WHICH MAY SUBJECT THE ACCESS TO SEDIMENT TRACKING. THIS SPECIFICATION IS TO BE DEVELOPED FOR POST-CONSTRUCTION USE, SOIL RESTORATION PRACTICES MAY BE APPLICABLE TO RESTORE CONSTRUCTION RELATED COMPACTION TO PRE-EXISTING CONDITIONS AND SHOULD BE VERIFIED BY SOIL PENETROMETER READINGS. THE PENETROMETER READINGS SHALL BE COMPARED TO THE RESPECTIVE RECORDED READINGS TAKEN PRIOR TO CONSTRUCTION, EVERY 100 LINEAR FEET ALONG THE PROPOSED ROADWAY.
- 10. TO ENSURE THAT SOIL IS NOT TRACKED ONTO THE LIMITED USE PERVIOUS ACCESS ROAD, IT SHALL NOT BE USED BY CONSTRUCTION VEHICLES TRANSPORTING SOIL, FILL MATERIAL, ETC. IF THE LIMITED USE PERVIOUS ACCESS IS COMPLETED DURING THE INITIAL PHASES OF CONSTRUCTION, A STANDARD NEW YORK STATE STABILIZED CONSTRUCTION ACCESS SHALL BE CONSTRUCTED AND UTILIZED TO REMOVE SEDIMENT FROM CONSTRUCTION VEHICLES AND EQUIPMENT PRIOR TO ENTERING THE LIMITED USE PERVIOUS ACCESS ROAD FROM ANY LOCATION ON, OR OFF SITE. MAINTENANCE OF THE PERVIOUS ACCESS ROAD WILL BE REQUIRED IF SEDIMENT IS OBSERVED WITHIN THE CLEAN STONE.
- 11. THE LIMITED USE PERVIOUS ACCESS ROAD SHALL NOT BE CONSTRUCTED OR USED UNTIL ALL AREAS SUBJECT TO RUNOFF ONTO THE PERVIOUS ACCESS HAVE ACHIEVED FINAL STABILIZATION.
- 12. PROJECTS SHOULD AVOID INSTALLATION OF THE LIMITED USE PERVIOUS ACCESS ROAD IN POORLY DRAINED AREAS, HOWEVER IF NO ALTERNATIVE LOCATION IS AVAILABLE, THE PROJECT SHALL UTILIZE WOVEN GEOTEXTILE MATERIAL AS DETAILED IN FOLLOWING NOTES.
- 13. THE DRAINAGE DITCH IS OFFERED IN THE DETAIL FOR CIRCUMSTANCES WHEN CONCENTRATED FLOW COULD NOT BE AVOIDED. THE INTENTION OF THIS DESIGN IS TO MINIMIZE ALTERATIONS TO HYDROLOGY, HOWEVER WHEN DEALING WITH 5%-15% GRADES NOT PARALLEL TO THE CONTOUR, A ROADSIDE DITCH MAY BE REQUIRED. THE NYS STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROLS FOR GRASSED WATERWAYS AND VEGETATED WATERWAYS ARE APPLICABLE FOR SIZING AND STABILIZATION. DIMENSIONS FOR THE GRASSED WATERWAY SPECIFICATION WOULD BE DESIGNED FOR PROJECT SPECIFIC HYDROLOGIC RUNOFF CALCULATIONS, AND A SEPARATE DETAIL FOR THE SPECIFIC GRASSED WATERWAY WOULD BE INCLUDED IN THIS PRACTICE, RUNOFF DISCHARGES WILL BE SUBJECT TO THE OUTLET REQUIREMENTS OF THE REFERENCED STANDARD. INCREASED POST-DEVELOPMENT RUNOFF FROM THE ASSOCIATED ROADSIDE DITCH MAY REQUIRE ADDITIONAL PRACTICES TO ATTENUATE RUNOFF TO PRE-DEVELOPMENT CONDITIONS.
- 14. IF A ROADSIDE DITCH IS NOT UTILIZED TO CAPTURE RUNOFF FROM THE ACCESS ROAD, THE PERVIOUS ACCESS ROAD WILL HAVE A WELL-ESTABLISHED PERENNIAL VEGETATIVE COVER, WHICH SHALL CONSIST OF UNIFORM VEGETATION (I.E. BUFFER), 20 FEET WIDE AND PARALLEL TO THE DOWN GRADIENT SIDE OF THE ACCESS ROAD. POST-CONSTRUCTION OPERATION AND MAINTENANCE PRACTICES WILL MAINTAIN THIS VEGETATIVE COVER TO ENSURE FINAL STABILIZATION FOR THE LIFE OF THE ACCESS ROAD.
- 15. THE DESIGN PROFESSIONAL MUST ACCOUNT FOR THE LIMITED USE PERVIOUS ACCESS ROAD IN THEIR SITE ASSESSMENT/HYDROLOGY ANALYSIS. IF THE HYDROLOGY ANALYSIS SHOWS THAT THE HYDROLOGY HAS BEEN ALTERED FROM PRE- TO POST-DEVELOPMENT CONDITIONS (SEE APPENDIX A OF GP-0-15-002 FOR THE DEFINITION OF "ALTER THE HYDROLOGY ... "), THE DESIGN MUST INCLUDE THE NECESSARY DETENTION/RETENTION PRACTICES TO ATTENUATE THE RATES (10 AND 100 YEAR EVENTS) TO PRE-DEVELOPMENT CONDITIONS.

#### **GEOGRID MATERIAL NOTES:**

- THE GEOGRID, OR COMPARABLE PRODUCT, IS INTENDED FOR USE FOR ALL CONDITIONS, IN ORDER TO ASSIST IN MATERIAL SEPARATION FROM NATIVE SOILS AND PRESERVE ACCESS
- 2. GRAVEL FILL MATERIAL SHALL CONSIST OF 1-4" CLEAN, DURABLE, SHARP-ANGLED CRUSHED STONE OF UNIFORM QUALITY, MEETING THE SPECIFICATIONS OF NYSDOT ITEM 703-02, SIZE DESIGNATION 3-5 OF TABLE 703-4. STONE MAY BE PLACED IN FRONT OF, AND SPREAD WITH, A TRACKED VEHICLE. GRAVEL SHALL NOT BE COMPACTED.
- 3. GEOGRID SHALL BE MIRAFI BXG110 OR APPROVED EQUAL. GEOGRID SHALL BE DESIGNED BASED ON EXISTING SOIL CONDITIONS AND PROPOSED HAUL ROAD SLOPES.
- 4. IF MORE THAN ONE ROLL WIDTH IS REQUIRED, ROLLS SHOULD OVERLAP A MINIMUM OF SIX
- 5. REFER TO MANUFACTURER'S SPECIFICATION FOR PROPER TYING AND CONNECTIONS.
- 6. LIMITED USE PERVIOUS ACCESS ROAD SHALL BE TOP DRESSED AS REQUIRED WITH ONLY 1-4" CRUSHED STONE MEETING NYSDOT ITEM 703-02 SPECIFICATIONS.
- BASIS OF DESIGN: TENCATE MIRAFI BXG110 GEOGRIDS; 365 SOUTH HOLLAND DRIVE, PENDERGRASS, GA: 800-685-9990 OR 706-693-2226: WWW.MIRAFI.COM


### GEOWEB MATERIAL NOTES:


- 1. THE GEOWEB, OR COMPARABLE PRODUCT, IS SUGGESTED FOR USE ON ROAD PROFILES EXCEEDING 10%. THE GEOWEB PRODUCT IS INTENDED TO LIMIT SHIFTING STONE MATERIAL
- INSTALLATION TO BE COMPLETED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS.
- 3. WHERE REQUIRED, A NATIVE SOIL WEDGE SHALL BE PLACED TO ACCOMMODATE ROAD CROSS SLOPE OF 2%. NATIVE SOIL SHALL BE COMPACTED TO MATCH EXISTING SOIL CONDITIONS.
- 4. GRAVEL FILL MATERIAL SHALL CONSIST OF 1-4" CLEAN, DURABLE, SHARP-ANGLED CRUSHED STONE OF UNIFORM QUALITY, MEETING THE SPECIFICATIONS OF NYSDOT ITEM 703-02, SIZE DESIGNATION 3-5 OF TABLE 703-4. STONE MAY BE PLACED IN FRONT OF, AND SPREAD WITH, A TRACKED VEHICLE. GRAVEL SHALL NOT BE COMPACTED.
- 5. GEOWEB SYSTEM SHALL BE PRESTO GEOSYSTEM GEOWEB OR APPROVED EQUAL. GEOWEB SHALL BE DESIGNED BASED ON EXISTING SOIL CONDITIONS AND PROPOSED HAUL ROAD SLOPES.
- 6. LIMITED USE PERVIOUS ACCESS ROAD SHALL BE TOP DRESSED AS REQUIRED WITH ONLY 1-4" CRUSHED STONE, SIZE 3A, MEETING NYSDOT ITEM 703-02 SPECIFICATIONS.
- 7. THE TOP EDGES OF ADJACENT CELL WALLS SHALL BE FLUSH WHEN CONNECTING. ALIGN THE I-SLOTS FOR INTERLEAF AND END TO END CONNECTIONS. THE GEOWEB PANELS SHALL BE CONNECTED WITH ATRA KEYS AT EACH INTERLEAD AND END TO END CONNECTIONS. REFER TO
- BASIS OF DESIGN: PRESTO GEOSYSTEMS GEOWEB; 670 NORTH PERKINS STREET, APPLETON. WI: 800-548-3424 OR 920-738-1222; INFO@PRESTOGEO.COM; WWW.PRESTOGEO.COM

MANUFACTURER'S SPECIFICATION FOR PROPER INSTALLATION, TYING AND CONNECTIONS.

#### **WOVEN GEOTEXTILE MATERIAL NOTES:**


- SPECIFIED GEOTEXTILE WILL ONLY BE UTILIZED IN PLACID SOILS. PLACID SOILS CONSIST OF POORLY DRAINED SOILS COMPOSED OF FINELY TEXTURED PARTICLES AND ARE PRONE TO RUTTING, PLACID SOILS ARE TYPICALLY PRESENT IN LOW-LYING AREAS WITH HYDROLOGIC SOILS GROUP (HSG) OF C OR D, OR AS SPCIFIED FROM AN ENVIRONMENTAL SCIENTIST, SOIL SCIENTIST, OR GEOTECHNICAL DATA.
- 2. THE CONCERN FOR POTENTIAL REDUCTION OF NATIVE INFILTRATION RATES DUE TO THE GEOTEXTILE MATERIAL WOULD NOT BE A SIGNIFICANT CONCERN IN POORLY DRAINED SOILS WHERE SEGREGATION OF PERVIOUS STONE AND NATIVE MATERIALS IS CRUCIAL FOR LONG TERM OPERATION AND MAINTENANCE.
- BASIS OF DESIGN: TENCATE MIRAFI RSI-SERIES WOVEN GEOSYNTHETICS; 365 SOUTH HOLLAND DRIVE, PENDERGRASS, GA; 800-685-9990 OR 706-693-2226; WWW.MIRAFI.COM






1. THE ROADSIDE DITCH SHALL BE DESIGNED IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND

 $\searrow$ LIMITED USE PERVIOUS ACCESS ROAD - 10% AND GREATER SLOPES WITH DITCH




GEOWEB SYSTEM
SCALE: N.T.S.



ackslashLimited use pervious access road - 0% to 10% slopes


VARIES (24' MAX.)



ackslashLimited use pervious access road - 10% and greater slopes

300 State Street, Suite 201 Rochester, NY 14614 585-454-6110

labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



#### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

NO:	DATE:	DESCRIPTION:		
Revisions				
PROJECT	NUMBER:	0004077		
		2231877		
DRAWN B	Y:	Med		
		MSB		
DRAWN B		MSB JJP		

**PERMIT** 

2 7/14/2025 REVISED PER TOWN & USACE COMMENTS

REVISED LANDSCAPING PLAN

DATE: **NOVEMBER 2023** 


Drawing Name:

**CONSTRUCTION DETAILS** 





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

1 11/1/2024 REVISED LANDSCAPING PLAN NO: DATE: DESCRIPTION: Revisions					
	1	11/1/2024	REVISED LANDSCAPING PLAN		
Revisions	NO:	DATE:	DESCRIPTION:		
	Revisions				
	UGAISIONS				
PROJECT NUMBER:		TOMBEIT.	2221877		

2231877 DRAWN BY:


PERMIT

NOVEMBER 2023

DRAWING NAME:


**DECOMMISSIONING PLAN** (PHASE 1)

DRAWING NUMBER:





labellapc.com



It is a violation of New York Education Law Article 145 Sec.7209, for any person, unless acting under the direction of a licensed architect, professional engineer, or land surveyor, to alter an item in any way. If an item bearing the seal of an architect, engineer, or land surveyor is altered; the altering architect, engineer, or land surveyor shall affix to the item their seal and notation "altered by" followed by their signature and date of such alteration, and a specific description of the alteration.

© 2020 LaBella Associates

### NY CDG GENESEE 6, LLC

800 GESSNER RD, SUITE 700 HOUSTON, TX 77024



### **GENESEE 6 SOLAR ARRAY**

8244 BATAVIA-STAFFORD TOWNLINE ROAD BATAVIA, NY 14020

1	11/1/2024	REVISED LANDSCAPING PLAN
NO:	DATE:	DESCRIPTION:
Revisions		
DDO IEOT		

2231877

PERMIT

NOVEMBER 2023

DRAWING NAME:

**DECOMMISSIONING PLAN** (PHASE 2)

DRAWING NUMBER: